# INC DYNO TEST ROOMS

# **Automotive Testing**

more. safely operate a dynamometer while providing excellent exhaust Designed and constructed of our 4" thick modular acoustical specifically designed to work with or without load control devices. dynamometer test room in your facility. Its features are building a professional high performance automotive ventilation and high performance sound reduction of 40 dBA or panels called PanI-Wall®, the INC Dyno Room will allow you to The INC Dyno Test Room is a pre-engineered modular system for

improves acoustical performance and eliminates interior noise our unique one-piece corner post. This assembly style is easy to one-piece H-joiner providing a structurally robust assembly. 4" thick acoustical panels that are joined together using our metal and are highly acoustically absorptive, which dramatically All interior surfaces of the Dyno Room consist of perforated sheet put together and provides a great degree of structural integrity. Room corners are built by butting perpendicular wall panels using The walls and roof of the room are assembled using our modular

assembly hardware. safety glass window, and all necessary joiners, trims, and seals and hardware. Two 42"x60" double glazed tempered swing, high performance acoustical personnel door and one 8'-0" Each standard room configuration includes one 4'-0" x 7'-0" single x 8'-0" vehicle entry door. Both are complete with heavy duty

significantly reduced through the exhaust assembly, maintaining silenced systems, so engine and exhaust noises will be expected maximum horsepower to be developed inside. We system is based in part on the size of the test room and the A key component in any dyno testing space is ventilation. Our removing exhaust gases and heat and supplying fresh air. the acoustical integrity of the Dyno Room while effectively to 10 times per minute. Our vent packages are high performance design our ventilation systems to provide a complete air change 8 related assembly components. The capacity of the ventilation frequency exhaust silencer stack, aerodynamic inlet grille and compatible ventilation systems include fans, heavy duty low

etc., and can be easily painted. Factory prime and painting of that provides protection from corrosive materials, solvents, fuels, your Dyno Room is available as an option. All components are fabricated of electro-galvanized sheet metal





WG. TITLE: PLANS AND ELEVATIONS N C industrial noise control, inc. 401Airport Road - North Aurora, IL 60542 - (800) 954-19 DYNO TEST ROOM

specialists in noise control products

TE: 2/11/2008

DRN. BY: MJR





# **Ventilation Details**

#### General Operation

SuperVent system consists of silenced exhaust stacks, roof mounted exhaust fans, fittings and inlet plenum. Fresh air is drawn through our silenced intake plenum. When properly installed and used our ventilation system will bring the CO levels in rate of 8 to 10 times per minute. the room during testing to a safe range of 5 to 10 ppm and exchange interior air at a

Please note that INC vent systems are designed to provide adequate heat and combustion gas removal from the room and fresh air make-up without temperature or humidity controls... not to simulate or provide airflow proportional to motorcycle speed under actual operating and specifications. conditions. Also note that some dynamometer installations may require additional pit or dyno ventilation that is not provided by INC. Please contact dynamometer manufacturer for details

#### Exhaust Ducting

weather cap suitable for the local environmental conditions to be provided by others. duct. The system is sized to allow for a maximum duct length from each fan of 15' heat and combustion gases. We recommend the use of round spiral or rectangular Any turns must be made using turning vanes to minimize duct pressure. Exterior The exhaust fans must be ducted to the exterior of your facility to properly remove

direction of the incoming air stream. made using turning vanes to minimize duct pressure and to maintain the proper flow bring intake air in from outdoors, it will be necessary to install non-restrictive ducting Intake air can be drawn from inside your facility requiring no additional ducting. To from the top of our inlet plenum to the exterior of your facility. Any turns must be

# 4. Electrical Requirements

The following electrical circuits are required:

- 230-460V 3-Phase 40 AMP for Exhaust Fans
- Included Components

Room Ventilation System: Then following components are included with the purchase of our SuperVent Dyno

- Two (2) interior silenced exhaust stacks with stands
- Two (2) 5 HP exhaust fans & mounting transitions
- Two (2) 6" diameter x 11' long hi-temp flexible exhaust hoses with flare ends and
- connector fittings
- One (1) fixed air intake grille One (1) silenced intake air plenum
- Adjustable exhaust hose stands are available as purchase options

## Supplied By Customer

SECTION C-C


It is the buyer's responsibility to provide all required ducting beyond the exit of the controls fans and the entrance of our inlet plenum as well as all fan motor starters and

PO#:	DWG. TITLE :		CUSTOMER:		_	REV. NO.		
	ME:		MER:		5	). DATE		
DRN. BY : MJR JOB : 2007-	VENTILAT			industri © 401 Airport Rd	specialists i			
	VENTILATION SECTION	INC AUTOMOTIVE DYNO TEST ROOM	PROJECT:	industrial noise control, inc. © 401 Airport Rd North Aurora, IL 60542 - 800/954-1998	specialists in noise control products	DESCRIPTION		

NOT TO SCALE


5/1/2007


THIS DRAWING IS THE PROPERTY OF INDUSTRIAL NOISE CONTROL, INC AND CONTAINS CONFIDENTIAL, PROPRIETARY INFORMATION. IT IS SUBJECT TO ALL COPYRIGHT LAWS AND SHALL NOT BE COPIED, USED OR DISCLOSED WITHOUT WRITTEN INC AUTHORIZATION.



## SECTION


SHOWING TYPICAL PANEL TO FLOOR CONNECTION





#### SECTION

SHOWING TYPICAL WALL PNL TO ROOF PUL CONNECTION



THIS DRAWING IS THE PROPERTY OF INDUSTRIAL NOISE CONTROL, INC AND CONTAINS CONFIDENTIAL, PROPRIETARY INFORMATION. IT IS SUBJECT TO ALL COPYRIGHT LAWS AND SHALL NOT BE COPIED, USED OR

SHOWING TYPICAL SECTION THRU PANEL JOINER

ENGINE DYNO CONSTRUCTION

SECTION

# ROOM CONSTRUCTION DETAILS

## Modular Wall & Roof Panels

outer solid steel face, and an inner perforated steel face with the spece between filled with a sound absorptive material. Panels shall be manufactured by Industrial Noise Control, Inc. (INC) of North Aurora, IL or equal. A. INC 4" thick Modular Acoustical Panels are intended to be used in indoor B. Modular panels shall be supplied in ready to use modules which are an all-welded box construction consisting of an internal welded panel frame, an cations requiring the construction of high STC acoustical test cells.

### II. COMPONENT DETAILS

A: Steel Materials: All steel used in the panel construction shall be galvanized coated. Stendard panels are electro-galvanized (EG) and may be painted without chemical wash. G-90 hot dipped galvanized is available as an option.

- B. Internal Panel Frame: Shall be formed channel of 18 gauge sheet steel
- C. Solid Panel Face: Shall be 14 gauge sheet steel.
- D. Internal Mass: Additional limp mass barrier placed bahind the solid panel face for increased low frequency TL.
- E. <u>Perforated Panel Face</u>: Shall be 22 gauge sheet steel perforated to an effective open area of 33% using 0.093° diameter holes on .156° steggered
- shall exhibit the following properties: F. <u>Absorptive Fill</u>: Shell be a 4" thick x 4LB density mineral fiber. Insulation shall meet ASTM C-423 Sound Absorption Coefficient of NRC-1.15. Insulation
- .Surface Burning Characteristics (ASTM E84, NFPA 255 & UL 723):
- Water Vapor Sorption (ASTM C1104): Less than 0.01% by volume.
- Temperature Resistence (ASTM C 411):
  Will not deteriorate up to +1200° F.

III. JOINT DETAILS

A. All panels are joined together using our one-piece steel H-Joiner.

# IV. PANEL CONSTRUCTION DETAILS

A. Module Size: Available in 24", 36" and 48" wide manufactured in lengths

B. Module Thickness: 4"

C: <u>Welded Module Construction</u>: Panels shall be constructed to retain their shape such that system components will fit together and function throughout the expected life of the structure and to allow dismantle and re-assembly a minimum of three times. The solid and perforated panel face sheets shall be spotweided or cinch locked to the internal channel frame on all perimeter edges at 6" to 6" on center. Spotwald or cinch locks shall have a minimum shear breaking load strength of 1350 lbs and an approximate diameter of

D. Internal Panel Reinforcement: When specified, an internal 18 gauge steel reinforcement channel shall be inserted between the solid and perforated face sheets, fastened to both, to provide additional panel rigidity.

# V. PANEL ACOUSTICAL PERFORMANCE

 All modular acoustical panels shall exhibit the following acoustical cteristics as tested and documented by an independent, accredited test

## Standard Construction Panel:

 
 Frequency (iz)
 125
 250
 500
 1000
 2000
 4000

 STL(dB)
 28
 30
 42
 51
 55
 59

 Sound Absorption
 .75
 1.05
 1.10
 1.07
 1.03
 94
 STC-44 NRC=1.0

Hard Construction Panel:

STL(dB) 28 43 55 63 63 69 STC-52 Sound Absorption Nat Applicable

# VI. DYNO ROOM ENTRY DOORS...

thickness and include full parimeter compression acoustical seets, a threshold seals, level swing hinges and non-locking lever latch set. A. All dyno room doors are of similar construction as the wall panels in a 4\*

# VI. PANEL STRUCTURAL CHARACTERISTICS

A. Standard Dyno Room panels are designed for interior applications.

# Wall panels can withstand 40 psf lateral loads.

- Roof panels, when assembled using H-Joiners can withstand a roof load capacity of 35 psf and will allow personnel access for maintenance, etc., but not intended for storage. etc., but is
- may be required. For installation in seismic zonas, additional seismic bracing and supports

# General Scope of Supply The Dyno Test Room scope of supply is limited to the four walls, roof, door, window and

LIABILITY

IMPORTANT DISCLAIMER & LIMITS OF

Room. All electrical components used in our Dyno Rooms are UL labeled, however, INC Dyno Test Rooms are not UL listed or fire labeled. these points is to be designed and provided by the purchaser. Fan controls, wiring, lighting, etc., and all other electrical requirements are to be provided by the purchaser appropriate assembly components and hardware for the basic room packages. When an INC vent system is purchased our scope of supply tarminates at the exit of the exitentates the exit of the exhaust fan and the inlet of the inlet fan (or sliencar if purchased) - all ducting beyond unless the INC electrical and lighting package is purchased in which case the purchases is responsible for bringing and connecting tha appropriate power supply the Dyno Test

Permits, Assessments and Other Fees

The purchaser obtains and pays for all building permits, licenses, public assessments, utility connections, occupancy fass and other fass required by any governmental authority or utility in connection with the purchase, installation and use of the Dyno Test. Room. The purchaser provides at his expense all plans and specifications required to obtain a building permit. It is the responsibility of the purchaser to ensure that all plans and spacifications comply with the applicable requirements of any governing building

# Code or Deed Restriction Compliance

required to comply with such codes, procedures or requirements which are not expressly set out as stated, must be paid by the purchaser. When any size, shape, general characteristics or design criteria of a Dyno Test Room are specified to INC, INC is not responsible for the suitability, adequacy, or legality of the Dyno Test Room or its equipment requirements, effect of (or on) existing structures, or fabrication procedures except those expressly set out in the Dyno Test Room order and specification documents. Costs of any additions, deletions, modifications, or changes that may be warrant the Dyno Test Room to comply with any building or zoning code requirements parmit requirement, deed restriction, design procedures, design load, materials or interpretations given to design standards, building codes, zoning codes, and deed restrictions encountared in the construction industry, the Manufacturer (INC) does not and accepted standards of industrial construction. However due to the wide INC dyno room components are designed and manufactured to meet generally used

#### Fire Safety Specific

meet ASTM E-84 Class I(A). The components are not fire reted or fire labeled. We strongly recommend that the purchasar contact the appropriate local municipality to determine if the installation of the Dyno Test Room will meet existing safety and fire code requirements. PLEASE INSTALL A FIRE EXTINGUISHER INSIDE THE DYNO All materials used in the construction of tha Dyno Tast Room are non-combustible and

#### Seismic Specific

Depending upon the seismic zone of the purchasers location and the local code requirements, additional saismic supporting structure may be required for the Dyno Test Room. Costs of any additions, deletions, modifications, or changes that may be required to comply with such codes, and the cost of the additionally required support

#### NOT TO SCALE DWG. TITLE: N C 9 401 Airport Rd. - North Aurora, IL 60542 - 800/954-1998 specialists in noise control products industrial noise control, inc. CONNECTIONS & DETAILS DRN. BY : MJR 5/1/2007 INC ENGINE DYNO TEST ROOMS SHT.: 4 OF 4 J0B: 2007-